



## SOLUTION

Installation of 84 units H800 type (hurricane ventilator) were installed over the roof area of the factory.

The exhaust rate of the 84 x H800 ventilators a 3m/s wind speed is 218,400m<sup>3</sup>/h. The air temperature and quality were significantly improved, the positive result of which was perceived by the personnel. The working environment was improved for the benefit of all.

**CO<sup>2</sup> FOOTPRINT SAVED**

68,542Kg/yr

## CLIENT

Union Print Malta Ltd.

## LOCATION

Marsa

35°52'14.03"N

14°29'23.06"E

## PRODUCTS USED

H800 Hurricane Ventilators

## OBJECTIVE

Increase factory air-quality, lower factory ambient temperature, improve working comfort.

## OVERVIEW

Energy Saved:

The ventilation system installed saves over 180 Kwh per day as compared to conventional ventilation using electrical power.

## CLIENT FEEDBACK

“Client Recommendation”